


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Kingman County, Sec. 14 Twp. 27 Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines SE-SE -NE
Lease Owner Morganstern & Spector Pipe & Supply
Lease Name Cannon Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 8-6-51 19
Application for plugging filed Nov. 10, 1959 19
Application for plugging approved Nov. 12, 1959 19
Plugging commenced 11 - 13 19 59
Plugging completed 11 - 17 19 59
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Viola Depth to top 4284 Bottom 4285 Total Depth of Well 4287 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	301	None
				5 2/2	4285	3021.87

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 4287' to 4275' and dumped 5 sacks of cement - mudded hole to 250' - set 10' rock bridge - dumped 20 sacks of cement - mudded to 35' - set rock bridge and dumped 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1960 1-19-60

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Morgenstern & Spector, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Morganstern & Spector*

SUBSCRIBED AND SWORN TO before me this 27th day of November, 1959

Notary 31st 1961

(Address) *Wichita, Kansas*
May P. Brown
Notary Public.

My commission expires



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


COPY

Company- LION OIL CO.
 Farm- Cannon No. 1

SEC. 14 T. 27 R. 10W
 SE SE NE

Total Depth- 4287
 Comm. 7-27-51 Comp. 8-6-51
 Shot or Treated. Acid 1000
 Contractor. R. W. Rine Drlg Co.
 Issued. 9-29-51

County Kingman
 KANSAS



CASING:

8 5/8" 301' cem w/250 sx.
 5 1/2" 4285' cem w/200 sx.

Elevation. 1749

Production. Physical Potential
 Pumped 188 bbls / 20% wtr

Figures Indicate Bottom of Formations.

sand	128
shale	305
red bed, shab	710
shale, shells	1450
lime	1645
shale, lime	3515
lime	3836
lime, shab	4023
chert	4040
lime	4105
lime, shab	4155
shale	4215
lime, shale	4280
lime	4286
lime	4287
Total Depth	
Tops:	
Lansing	3502
Miss.	4023
Viola	4284

RECEIVED
 STATE CORPORATION COMMISSION

NOV 25 1959

CONSERVATION DIVISION
 Wichita, Kansas