


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 26 Twp. 29S Rge. (E) 13 (W)
Location as "NE/CNW%SW%" or footage from lines NE NE SW
Lease Owner Natural Gas and Oil
Lease Name Larrison Well No. 1
Office Address P.O. Box 1150, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed April 10 19 57
Application for plugging filed May 17 19 62
Application for plugging approved May 18 19 62
Plugging commenced June 5 19 62
Plugging completed June 9 19 62
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production October 31 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation Arb.-Lans Depth to top 4678 arb Bottom 4683 arb Total Depth of Well 4690 Feet
Show depth and thickness of all water, oil and gas formations. 4178 Lans 4181 Lans
4096 Lans 4100 Lans

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	375	None
				5 1/2	4690	3815'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 4690' - 4660' - 5 sacks cement
- 4660' - 360' - Mud
- 360' - 350' - Rock bridge
- 350' - 290' - 20 sacks cement
- 290' - 35' - Mud
- 35' - Base - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

6-26-62 JUN 26 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Company
Address P.O. Box 114 - Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. B. Steele, Jr. (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.
P.O. Box 1150, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 19 62

Richard R. Beach Notary Public.

My commission expires July 27, 1953

Location No. 1
 Lot: 12 1/2 1/2
 Sec: 26-278-134
 Pratt County, Kansas
 Company: Natural Gas & Oil Company
 Contractor: Hosaker-Davis Drilg. Co.

Core: 3-8-37
 Comp: 4-3-37
 Rotary Total Depth: 4690'
 Casing: 8-5/8" at 375'
 3-1/2" at 4690'

0	180	Sand
180	250	Red Bed & Shale
250	375	Shale & Red Bed
375	570	Red Bed & Shale
570	1330	Shale & Shells
1330	1920	Shale & Lime
1920	2140	Lime
2140	2453	Lime & Shale
2453	2585	Shale
2585	2705	Shale & Lime
2705	2855	Shale, Lime & Shells
2855	3085	Shale & Lime
3085	3185	Lime & Shale
3185	3475	Shale & Lime
3475	3800	Lime & Shale
3800	4384	Lime
4384	4444	Lime & Shale
4444	4539	Lime
4539	4557	Lime & Chert
4557	4690	Lime
4690		Total Rotary Depth.

8-5/8" casing cemented at
 375' with 350 sacks cement,
 2% calcium chloride and
 2% Jel.

CONSENTED TO BY
 WICHITA, KANSAS

5-1/2" casing cemented at
 4690' with 150 sacks
 cement.

I certify that this is the true and correct copy of the
 above log to the best of my knowledge.


 H. E. Forbes

Subscribed and sworn to before us this 5th day of
 April, 1937.


 Kenneth C. Fischer, Notary Public

My commission expires: 6-21-39