

DRILLER'S LOG  
DRIPPING LOG

COMPANY: J. N. HUBER CORPORATION LOCATION: SE SE SW 7-25S-13W  
 CONTRACTOR: FABCO DRILLING, INC. Stafford County, Kansas  
 FARM NAME: #1 KACHELMAN "B" PRODUCTION: DRY & ABANDONED.  
 COMMENCED: 1-26-51 ELEVATION: 1964 rotary bushing.  
 COMPLETED: 3-16-51

OLD WELL DRILLED DEEPER

Old Total depth	4086	<u>TOPS</u>
Shale	4162	Simpson 4260(-2296)
Chert	4197	Arbuckle 4315(-2351)
Cherty limestone	4242	
Crystalline limestone	4260	Cored 4198-4205, recovered 7' gray finely crystalline to dense limestone and gray chert, few thin green shale seams in top 1'.
Dense sandy limestone	4262	Cored 4205-33, recovered 28' gray finely crystalline to dense limestone and gray chert, occasional show free oil along fractures in bottom 2'.
Green shale	4286	Cored 4233-61, recovered 28'.
Sandy shale	4315	9' gray finely crystalline to dense limestone and gray chert, occasional free oil along fractures in top 5'.
Dolomite	4345 T.D.	18' brown to buff coarsely crystalline limestone, very little porosity, show free oil in top 3'.
		1' dense brown limestone with medium, round sand grains embedded.
		Drill Stem Test 4221-61, open 1 hour, recovered 10' mud with rare spots of oil, no bottom hole pressure.
		Cored 4261-89, recovered 28'.
		1' dense limestone with medium, round sand grains embedded.
		24' green shale
		3' sandy shale, no shows.
		Cored 4289-4317, recovered 28'.
		25' green shale with sandy shale zones.
		2' gray finely crystalline dolomite, fair porosity in small vugs, strong sulphur odor, no stain.
		Cored 4317-45, recovered 28'.
		10' buff finely crystalline dolomite & gray white banded chert, few thin green shale seams, some vuggy porosity in dolomite.
		4' buff, coarsely crystalline dolomite, fair porosity in vugs.
		10' buff to gray very finely crystalline slightly sandy dolomite, with gray chert nodules and green shale partings.
		4' gray finely crystalline very sandy dolomite.
		Total depth 4345, DRY & ABANDONED.

RECEIVED  
STATE CORPORATION

STATE OF KANSAS )  
 ) SS  
COUNTY OF SEDGWICK)

MAR 29 1951

3-29-51

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above is a true and correct copy of the log of the #1 Kachelman "B", located in the Southeast Quarter of the Southeast Quarter of the Southwest Quarter (SE SE SW) of Section Seven (7), Range Twenty-five (25) South, Range Thirteen (13) West, of the 6th P.M. Stafford County, Kansas

E. A. Huffman  
E. A. Huffman, District Manager  
J. N. HUBER CORPORATION

Subscribed and sworn to before me this 28 day of March, 1951

Kerith J. Benes  
Notary Public