

DRILLER'S LOG

COMPANY: J. M. Huber Corp. & Fabco
CONTRACTOR: Fabco

LOCATION: SW SE SW 7-25S-13W
Stafford County, Kansas

FARM NAME: #1 Kacholman "B"

ELEVATION: 1962 derrick floor

COMMENCED: 6-25-50

CASING USED: 8" at 395' with 225 sacks cement

COMPLETED: 6-25-50

5 1/2" at 4075 with 75 sacks.

Sand	50	<u>HADING TOPS</u>
Shale & red bed	200	
Shale	590	Raebrar
Shale & red bed	820	Brown Lime
Anhydrite	850	Lensing
Shale & shells	1350	D.S.T.
Salt	1405	3895-3920, open 1 hour, recovered 6' of mud.
Shale & salt	1470	show free oil with odor 3936-41, 3943 & 3946'.
Shale & shells	1610	
Shale & lime	1820	D.S.T. 3935-46, open 1 hour, recovered 30' of rotary mud.
Lime & shale	2335	Bass Kansas City 3952
Shale & lime	2590	Marmaton Chert 4007
Shale & shells	2775	Viola 4056
Shale	2975	D.S.T. 4074-83, open 1 hour, gas to surface in 5 minutes,
Shale	3105	recovered 2,220' of oil.
Shale & lime	3280	
Lime	3300	Drilled plug. After swabbing for 16 hours,
Lime & shale	3363	well produced 25 barrels oil/6 hours. Last 3
Lime	3476	hours of test, well leveled off at rate of 30
Gray Lime	3498	barrels oil per hour. Casing pressure varied
Lime & shale	3695	from 400# to 210#.
Lime	3948	
Lime & shale	4022	Acidized with 500 gallons acid through tubing.
Lime & chert	4070	Swabbed 27 barrels oil plus 10 barrels water in
Cherty Lime	4085	1 1/4 hours.
Total depth	4085	

Potential: 105 barrels oil plus 250 water per day. COMPLETED.

STATE OF KANSAS }
CO. OF SEDGWICK)
COUNTY OF SEDGWICK)

APR 14 1951
CO. OF SEDGWICK DIVISION
Wichita, Kansas

4-14-51

I, Edward A. Huffman, hereby certify that the above is a true and correct copy of the log on the No. 1 Kacholman "B", located in the Southeast Quarter of the Southeast Quarter of the Southwest Quarter (SW SE SW), Section Seven, (7), Township Twenty-five (25) South, Range Thirteen (13) East, Stafford County, Kansas.

Edward A. Huffman
Edward A. Huffman, Manager
J. M. HUBER CORPORATION

Subscribed and sworn to before me this 11 day of Sept., 1950

Bartholomew Rees
Notary Public

By Commission expires: January 26, 1953

PLUGGING

FILE SEC 7 T 25 R 13W
BOOK PAGE 7 VOLUME 14