

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED

STATE CORPORATION COMMISSION

FEB 29 1968

CONSERVATION DIVISION

Wichita, Kansas

2-29-68

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 21, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply, Inc. has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas 67530

Lease Name: Hilger-Cron Well No. 1

Location: NE NE NE Sec. 30 Twp. 26 Rge. 4 (E)(W) X

County: Reno Total Depth 4050' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

Fill hole with sand to 2940' and cement with 5 sacks.

Fill hole with mud to 240'. Set rock bridge from 240' to 230' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent