

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Nov. 14, 1962

RECEIVED  
 STATE CORPORATION COMMISSION  
 11-26-62  
 NOV 26 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Ron Harris of Gayle E. Toland has this  
 date requested permission to plug the following described well:

Mr. Ron Harris guarantees payment of the plugging fee.

Operator's full Name: SUN OIL CO.  
Gayle E. Toland

Complete Address: 412 UNION NAT' Bldg. Wichita, KANSAS  
~~Box 4336 Oklahoma City, Oklahoma,~~

Lease Name: Martin #1 Well No. #1

Location: SE SE SE Sec. 19 Twp. 26S Rge. 4 (E) (W) W

County Reno County Total Depth 4025' Oil Well X  
 Abandoned

Gas Well     Input Well     SWD Well     D & A     Lost Hole    

Mr. Ron Harris was instructed to plug the well as follows:

~~4025' of 5 1/2" long string. Plugged back to 4016'. Perforated  
 between 3963' and 3967'. Pipe sanded to 3950' and 5 sacks cement.  
 286' of 8 5/8" surface pipe circulated with cement. Hole  
 filled with heavy mud to 200' and 10' rock bridge and 20 sacks  
 cement. Hole filled to 40' with heavy mud, 10' rock bridge  
 and 10 sacks cement to base of cellar.~~

Very truly yours,

*Hermon Justus*  
 Conservation Division Agent