

State of Kansas



WM. H. AVERY Governor
WILLIAM E. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212
WICHITA, KANSAS 67202
RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1966
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 21, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Walters Drilling Co. and Oil Property Management Inc.

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name: Back "A" Well No. 1

Location: C SW NW Sec. 22 Twp. 26 Rge. 4 (E) (W) X

County Reno Total Depth 3310' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

Fill hole with mud to 140'. Push plug and 1/4 sack hulls to 140' and

cement hole with 25 sacks through drill pipe. Fill hole with mud to

40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent