

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 3, 1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Robert Miller of Graves Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Brad's Petroleum Company

Complete Address: 4040 N. Lincoln, Oklahoma City, Oklahoma

Lease Name: White Well No. 1

Location: C NW NE Sec. 31 Twp. 25 Rge. 6 (E) (W) X

County: Reno Total Depth 4300' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

Fill hole with heavy mud. Push plug to 600'. Pump 25 sacks cement
through drill pipe at 600'. Pump 25 sacks cement through drill pipe
at 235'. Push plug and $\frac{1}{2}$ sacks hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1968
CONSERVATION DIVISION
Wichita, Kansas

12-10-68

Very truly yours,

[Signature]
Conservation Division Agent