

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 18 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed June 29, 1967.

Operator's Full Name Graybol Oil Corporation

Complete Address 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma

Lease Name Gibbens Well No. # 1

Location C NE SW Sec. 22 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 4410'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Graybol Oil Corporation

Address 2200 National Bank of Tulsa, Tulsa, Okla. License No.       

Operation Completed: Hour 5:00 P.M. Day 16th Month July Year 1967

The above well was plugged as follows:

296' of 8 5/8" surface pipe, cement circulated with 220 sacks. Hole was  
filled with drilling mud to 250', 1st cementing plug, bridged with 2 sacks  
of dry cement and 1/2 sack of hulls on fluid at 250', and cemented with 23  
sacks from 250' to 165'. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on  
fluid at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 7/18/67

INV. NO. 5985-W