

15-155-60003-00-01

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Woodman & Iannitti Oil Company

Complete Address Box 308 Great Bend, Kansas 67530

Lease Name Hilger-Con Well No. # 1

Location NE NE NE Sec. 30 Twp. 26 Rge. (E) 4 (W)

County Reno Total Depth 3291'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated OWWO When Woodman & Iannitte Oil Co. Drilled Well.

Plugging Contractor Rockhold Engineering, Inc.

Address Great Bend, Kansas License No. # 670

Operation Completed: Hour 10 PM Day 26 Month 6 Year 73

The above well was plugged as follows:

8 5/8"-247'-Circulated w/cement. 5 1/2"-3307'-Cemented. Top Perf. 3226'.

Sand hole to 3200'. 5 Sax. cement at 3200'. Mud to 270'.

Bridge 270' to 255'. 25 Sax. Cement at 255'. Mud to 40'.

Bridge 40' to 30'. 10 Sax. Cement 30' to 0.

Pulled 2810'-5 1/2"-Pipe. No Fluid in hole, or any gas showing.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6/28/73
INV. NO. 7563-11

Signed: [Signature]
Well Plugging Supervisor