

To: 1040648
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-17 API NUMBER 15-097-20,658-0000 122

C NW NW, SEC. 19, T. 27 S, R. 16 W/E
4620 feet from S section line

4620 feet from E section line

Lease Name Burtsfield Well # 3-19

County Kiowa

Well Total Depth 4680 152.10 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 407

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Operator: Farrar Pump & Supply Co. Inc.

Name & Address P.O. Box 209

Medicine Lodge, KS 67104

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 17 Month: 4 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

was: 4 1/2" at 4671' w/200 sx cement, PBTD 4310', Perfs at 4111-17'

1st plug sand back to 4060' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 17 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4060' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

DATE 4-28-92

INV. NO. 35075

Signed Stephen J. Pfeiffer
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
APR 24 1992
CONSERVATION DIVISION
Wichita, Kansas