

To: 1031310 1-31  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,886-0000  
NW NW SW, SEC. 17, T 27 S, R 16 W/E  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Sneed Well # 1

Operator: Beren Corporation

County Kiowa

Name &

Address P.O. Box 723

Well Total Depth 4684 152.23 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well  Gas Well  Input Well  SMD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 31 Month: 1 Year: 1995

Plugging proposal received from Richard

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 4683' w/250 sx cement, Perfs at 4594-98, 4102-04, 4620-30'

1st plug sand back to 4050' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

RECEIVED  
FEB 06 1995  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 31 Month: 1 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 4 sx cement on top of

sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2420' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-6-95  
INV. NO. 42163  
observe this plugging.

Signed Steve Durrant  
(TECHNICIAN)