

1 090267

*RJ*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,848-0000  
C SE NW, SEC. 13, T 27 S, R 16 W

3300 feet from ~~XX~~S section line  
3300 feet from ~~XX~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028

Lease Name Rose Well # 2-13A

Operator: Imperial Oil Co.

County Kiowa 150.15

Name & Address 720 Fourth Financial Center

Well Total Depth 4620 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 3 Month: January Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4619' PBD 4470' Perfs at 4431-38'

1st plug sand back to 4380' and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 120 sx cement

Plugging Proposal Received by *R. Bartlett*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:35 pm Day: 3 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 125 psi

1-7-85  
11 AM 07 JAN

Remarks: Recovered 2236' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% Wchita, Kansas  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-18-85

Signed *R. Bartlett*  
(TECHNICIAN)

INV. NO. 6596