

1052025

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 097-20,872-0000
SE NE SW, SEC. 12, T 27 S, R 16 WXX
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

3-7

Operator License # 5364
Operator: Beren Corporation
Name & Address: P.O. Box 723
Hays, KS 67601-0723

Lease Name Kelton A Well # 2
County Kiowa
Well Total Depth 4660 151.45 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 448

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 10 a.m. Day: 7 Month: 3 Year: 19 96

Plugging proposal received from George Juergenson
(company name) Beren Corporation (phone) 913-628-6101

Work: 4 1/2" at 4659' w/250 sx cement, PBTD 4615', Perfs at 4227-30, 4184-88, 4436-40'
1st plug set CIBP at 4100' w/2 sx cement on top,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

3-11-96

RECEIVED
KAISAS
KRP
COMM
1996
M/R
None
3/11/96

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____

Operations Completed: Hour: 11 a.m. Day: 7 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' with 2 sx cement on top,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2360' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE MAR 13 1996
INV. NO. 45036

Signed Richard M. Lucey (TECHNICIAN)