

To: 1 090786 3-12
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 097-20,895-0000
C SE NE, SEC. 12, T 27 S, R 16 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5364
Operator: Beren Corporation
Name:
Address P.O. Box 723
Hays, KS 67601

Lease Name Kelton Well # 3
County Kiowa 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 449

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 9:30 a.m. Day: 12 Month: 3 Year: 19 97

Plugging proposal received from Manny Boatwright
(company name) Mike's Testing & Salvage (phone) 316-938-2943

was: 4 1/2" at 4599' w/250 sx cement, Perfs at 4415-19'
1st plug sand back to 4365' and dump 4 sx cement on top of sand through bailer,
2nd plug at 1050' with 50 sx cement,
3rd plug at 470' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:30 a.m. Day: 12 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3345' and dumped 4 sx cement on top,
2nd plug at 1075' with 50 sx cement,
3rd plug at 520' with 50 sx cement,
4th plug at 100-0' with 30 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2425' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(Check) If you wish to observe this plugging.

DATE MAR 18 1997

INV. NO. 47765

Signed _____ (TECHNICIAN)

MAHSA RECEIVED
1997 MAR 18 12:03
MAHSA'S CORP COMM