

To: 1 090783 3-7
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 097-20,875-0000
C NE NE, SEC. 12, T 27 S, R 16 WEX
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5364
Operator: Beren Corporation
Name:
Address: P.O. Box 723
Hays, KS 67601

Lease Name: Kelton Well # 2
County: Kiowa 147.87
Well Total Depth: 4550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 493

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor: Mike's Testing & Salvage, Inc. License Number: 31529
Address: P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 11 a.m. Day: 7 Month: 3 Year: 19 97
Plugging proposal received from: Manny Boatwright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2945

Work: 5 1/2" at 4549' w/250 sx cement, Perfs at 4196-4202, 4159-64, 4025-30'
1st plug sand back to 4075' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 1000',
3rd plug pump 50 sx cement at 520',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by: Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 7 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3975' and dumped 5-sx cement on top of sand through bailer,
2nd plug pulled to 1050' and spotted 50 sx cement,
3rd plug pulled to 520' and spotted 50 sx cement,
4th plug pulled to 40' and spotted 10 sx cement.
Stayed full.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3001' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE MAR 11 1997
WV. NO. 47718
3-7

Signed: _____
(TECHNICIAN)

KANSAS RECEIVED
CORP COMM
MAR 10 P 3:50