

To: 1 040823 1-24
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,852-0000
C NE SE, SEC. 12, T 27 S, R 16 W/EX
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Winklepleck Well # 3-12

Operator: J. Mark Richardson

County Kiowa

Name & Address 155 N. Market, Ste. 830

Well Total Depth 4605 149.66 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 401

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number 31201

Address 155 N. Market, Ste. 830, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 24 Month: 1 Year: 19 94

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

vars: 4 1/2" at 4604' w/200 sx cement, BP 2848', Perfs at 4482-4502, 2447-2882'

1st plug sand back to 2400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

STATE APPROVED

FEB - 1 1994

Plugging Proposal Received by

Duane Rankin

CONSERVATION DIVISION
Wichita, Kansas

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 24 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 2400' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2220' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 2-4-94

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 39875