

1 051281

3-27

171 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20882-0000

C NW SE, SEC. 12, T 27 S, R 16 N/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Winklepleck Well # 4-12

Operator: J. Mark Richardson

County Kiowa 156.00

Name & Address 115 No. Market

Well Total Depth 4800 feet

Suite 840

Conductor Pipe: Size _____ feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 412

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensberg Well service License Number 5414

Address 309 E Kansas P.O. Box 632 Greensberg KS 67054

Company to plug at: Hour: 10:00 a Day: 27 Month: March Year: 1990

Plugging proposal received from Carl Shields

(company name) J. Mark Richardson (phone) 316-723-3292

were: 4 1/2 at 4799 PBD 4660' Perts @ 4510-4515

1st plug sand back to 4460 + dump 4sx cement on top sand through a bailer

2nd plug pump 4sx hulls, 10sx gel, 50sx cement, 10sx gel, 1sx hulls, 8 5/8 plug and 125sx cement

Plugging Proposal Received by Glen Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40p Day: 27 Month: March Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' + dumped 4sx cement on top of sand through a bailer

2nd plug pumped 4sx hulls, 10sx gel, 50sx cement, 10sx gel 1sx hulls, 8 5/8 wiper plug and 125sx cement

Maximum pressure 350 psi and shut in pressure 50 psi

Remarks: Used 60/40 p.e.z. 6" gel by Allied Recovered 3160' of 4 1/2
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-6-90

INV. NO. 27808

3-27

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
4-02-90

Signed Richard W. Lacey
(TECHNICIAN)