

To: 1 041156  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-097-20,831-0000  
150' SE of  
C SE SW, SEC. 12, T 27 S, R 16 W  
585 feet from S section line  
3225 feet from E section line

3-8

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5364  
Operator: Beren Corporation  
Name & Address: 970 Fourth Financial Center  
Wichita, KS 67202

Lease Name Kelton A Well # 1  
County Kiowa  
Well Total Depth 4589 149.14 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 445

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service, Inc. License Number 5893  
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 11:45 a.m. Day: 8 Month: 3 Year: 1996

Plugging proposal received from George Ferguson  
(company name) Beren Corporation (phone) 913-628-101

were: 5 1/2" at 4588' w/250 sx cement, Perfs at 4300-02, 4495-4501, 4560-64, 4568-75'  
1st plug set CIBP at 4200' and dump 2 sx cement on top through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p. Day: 8 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4200' and dumped 2 sx cement on top through  
bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 550 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2454' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 26 1996  
INV. NO. 45121

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
ANSAS  
CORP  
13  
MAR 13 1996