

1040986 7-28

API NUMBER 15- 097-20,700-0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
30 S. Market, Room 2078
Wichita, KS 67202

SE SE SE, SEC. 10, T 27 S, R 16 W NE
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Hendricks B Well # 1

Operator: BEREN Corporation

County Kiowa 150.12

Name & Address P.O. Box 723

Well Total Depth 4619 feet

Hays, KS 67601-0723

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 28 Month: 7 Year: 19 95

Plugging proposal received from David Brady

(company name) Mike's Testing & Salvage (phone) 316-938-2943

Work: 4 1/2" at 4618' w/250' sx cement, Perfs at 4543-46, 4548-52'

1st plug sand back to 4490' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 28 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4490' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped

Maximum pressure 400 psi and shut in 50 psi.

AUG 01 1995

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE AUG 02 1995

INVT. NO. 43228
7-28

Signed [Signature] (TECHNICIAN)