

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20790-00-00
Spot: CN2N2NE Sec/Twnshp/Rge: 7-27S-16W
330 feet from N Section Line, 1320 feet from E Section Line
Lease/Unit Name: MATTHEWS Well Number: 2
County: KIOWA Total Vertical Depth: 4660 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: P.O. BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: 8151.45
Surface Casing: Size 8.625 feet: 405 WITH 325 SX CMT
Production: Size 4.5 feet: 4659 WITH 250 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/14/2002 1:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP 50 SX CMT & 400# HULLS ON BOTTOM. PLUG AT 1100' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/14/2002 2:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:
PBTD 4620'. PERFS AT 4566-77, 4554-57, 4536-39, 4510-14'. PUMP 50 SX CMT & 200# HULLS. PRESSURED TO 2400# & SHUT IN FOR 4 HOURS. 1ST PLUG PUMP 10 SX GEL & 50 SX CMT AT 1,100'. 2ND PLUG PULL TO 450' & PUMP 50 SX CMT. 3RD PLUG PULL TO 40' & PUMP 10 SX CMT. GOOD CIRCULATION.

RECEIVED
NOV 18 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2430' OF 4 1/2" CASING.

Plugged through: CSG

District: 01 Signed _____

RECEIVED
NOV 15 2002
KCC Dodge City

[Signature]
(TECHNICIAN)

INVOICED
DATE 11-19-02
INV. NO. 2003060834

Form 22/B