

1 030184

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Not available  
NW, SEC. 4, T 27 S, R 16

660 feet from N/SX section line  
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5414

Lease Name Baker Well # 1 SWD  
County Kiowa

Operator: J. Mark Richardson  
Name & Address 640 Century Plaza  
Wichita, KS 67202

Well Total Depth 4565 148.36 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 380

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_  
Address Box 31, Russell, KS 67665

Company to plug at: Hour: 10:00 am Day: 23 Month: May Year: 19 84

Plugging proposal received from Carl Shield  
(company name) J. Mark Richardson (phone) 316-262-3192

were: 4 1/2 set at 4565

pump down 8 5/8" annulus - 7 sx gel, and 200 sx cement

pump down 4 1/2" 1 sx hulls, 20 sx cement, 11 sx gel and 100 sx cement.

Plugging Proposal Received by Steve Almont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 am Day: 23 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4565'

pump down 8 5/8" annulus - 7 sx gel, and 200 sx cement - 0 Vacuum

pump down 4 1/2" - 1 sack hulls, 20 sx cement, 11 sx gel and 100 sx cement

0 pressure maximum and shut in

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 5-29-84

Signed Steve Almont  
(TECHNICIAN)

INV. NO. 1688  
5-23