

No: 1 051254
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-28 274
API NUMBER 15-097-20,728-000
NE NE NW, SEC. 3, T 27 S, R 16 W/E
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414
Operator: J. Mark Richardson
Name & Address: 155 North Market, Suite 840
Wichita, KS 67202

Lease Name Jewett Well # 2
County Kiowa 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 401

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number
Address 303 East Kansas, Greensburg, KS 67054

Company to plug at: Hour: 10:30 a.m. Day: 28 Month: 12 Year: 19 89

Plugging proposal received from Carl Schield
(company name) Greensburg Well Service (phone) 316-723-2204

were: 4 1/2" at 4548' Perfs at 4511-4516, 4486-92, 4499-4505' Elevation 2083' GL
1st plug sand back to 4430' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:45 p.m. Day: 28 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 ROZMIX gel by B.J. Titan. Recovered 2290' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-22-90
INV. NO. 27039
12-28

Signed Richard W. Lacey (TECHNICIAN)