

1 120329

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,581-0000

C. NE SW, SEC. 1, T 27 S, R 16 W/R

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Healy Well # 1

Operator: Beren Corporation

County Kiowa 149.50

Name & Address Box 723

Well Total Depth 4600 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 24 Month: 10 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4599' Perfs at 4497-4506'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 24 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4450' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by D.J. Titan. Recovered 2500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-2-89

INV. NO. 26298

10-24

11-1-89

Signed Deane Rankin
(TECHNICIAN)