

To: 1 040398  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-25 308  
API NUMBER 15-097-20,849-0000  
C SE SE, SEC. 1, T 27 S, R 16 W/E  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5364  
Operator: Beren Corporation  
Name & Address: 970 Fourth Financial Center  
Wichita, KS 67202

Lease Name Healy Well # 2  
County Kiowa 149.83  
Well Total Depth 4610 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 454'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service, Inc. License Number 5893  
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:45 a.m. Day: 25 Month: 1 Year: 19 90

Plugging proposal received from Bruce Wagoner  
(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4609' CIBP at 4100' Perfs at 4164-90, 4198-4202, 4515-23, 4010-14'  
1st plug sand back to 3960' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1990

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 25 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3960' and dumped 5 sx cement on top of  
sand through bailer.

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, and 100 sx cement.

(No wiper plug, unable to get braden head off, shut braden head in and pumped through head.)

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2269' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 05 1990

INV. NO. 27313

1-25

Signed Stephen L. Pfeifer  
(TECHNICIAN)