

1041367

TO:
STATE CORPORATION COMMISSIONAPI NUMBER NA 15-151-19001-00-00
NW NE NE SEC. 25, T 27 S, R 11 WCONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CUNNINGHAM "B" UNIT WELL # 11

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATTOPERATOR LICENSE # 3880WELL TOTAL DEPTH 3477 113.00 FEETOPERATOR: K.C. RESOURCES, INC. PRODUCTION CSG: SIZE 5 1/2" @ 3463' WITH 225 SXNAME AND PO BOX 1118 SURFACE CASING: SIZE 8 5/8" @ 344' WITH SXADDRESS CARDIFF, CA 92007ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR PRATT WELL SERVICE, INC LICENSE NUMBER 5893ADDRESS PO BOX 847, PRATT, KS 67124COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 23 MONTH: 09 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM ROD HOVLAND W/K.C. RESOURCES(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531WERE: OPEN HOLE AT 3463-3477

SET CIBP @ 3380' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. PUMP DOWN 5 1/2" X
8 5/8" ANNULUS WITH 80 SX CEMENT. MAXIMUM PRESSURE AT 300#. SHUT IN WITH 100#. RUN TUBING
INSIDE 5 1/2" CASING TO 600'. CIRCULATED 5 1/2" CASING WITH 80 SX CEMENT FROM 600' TO SURFACE.
LAI D TUBING DOWN AND TOP OUT 5 1/2" CASING WITH 24 SX CEMENT.

INDEXED PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFERPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE DATE 10-13-99 OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 23 MONTH: 09 YEAR: 1999ACTUAL PLUGGING REPORT

SET CIBP @ 3380' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. PUMPED DOWN 5 1/2"
X 8 5/8" ANNULUS WITH 80 SX CEMENT. MAXIMUM PRESSURE AT 300#. SHUT IN WITH 100#. RUN
TUBING INSIDE 5 1/2" CASING TO 600'. CIRCULATED 5 1/2" CASING WITH 80 SX CEMENT FROM 600' TO
SURFACE. LAID TUBING DOWN & TOP OUT 5 1/2" CASING WITH 24 SX CEMENT.

REMARKS: USED 60/40 POZMIX-48 GEL BY UNITED CEMENTING & ACID CO., INC.NO CASING RECOVERED. PIPE HUNG UPS IN HOLE OR SQUEEZED IN

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING: 05 1999

SIGNED

Stephen J. Pfeifer
(TECHNICIAN)

FORM CP-2/3

CONSERVATION DIVISION
WICHITA, KS