

JUN 23 1987

2 050552

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drilled & Comp. 3-5-72

NE NE NW, SEC. 14, T 27 S, R 10 WXR

TECHNICIAN'S PLUGGING REPORT

_____ feet from S section line

_____ feet from E section line

Operator License # 5992

Lease Name McMichael Well # 1

Operator: Kelso--Patton Oil

County Kingman 130.98

Name & Address 673 E. 5yh

Well Total Depth 4030 feet

Hoisington, KS 67544

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, KS

Company to plug at: Hour: _____ Day: _____ Month: 6 Year: 19 87

Plugging proposal received from _____

(company name) _____ (phone) _____

work: 5p" casing was set at 4015' with 125 sxs cement. Open hole to 4030 (15')

Sand back to 3960 and dump 6 sxs cement. Shoot and pull pipe. Redi-mix 300' to

surface.

Plugging Proposal Received by Warren Kirkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00pm Day: 23 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT Sanded back to 3960 and dumped 6 sxs cement w/dump bailer.

Shot and pulled 3000 of 5 1/2" casing. Gressel Oilfield Service ran 2 3/8" tubing to 287'

and Allied Cementing Co. circulated cement from 287' to surface.

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing 60/40 poz 6% gel
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Glen L. Ward
(TECHNICIAN)

DATE 7-1-87

INV. NO. 17396