

To: 2 040359  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-095-20803-0000  
C NE SW, SEC. 14, T 27 S, R 10 W/EX  
1980 feet from S section line  
3300 feet from E section line  
Lease Name Sale Well # A-1  
County Kingman 78.65  
Well Total Depth 2420 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 262

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992  
Operator: Patton Oil Company  
Name & Address 672 W. 4th  
Hoisington, KS 67544

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase, KS

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Dallas  
(company name) Kelso Casing Pulling (phone) \_\_\_\_\_  
were: 4 1/2" @1922, PBD @1888, Perf. 1612-40

35 sxs on bottom, 200# hulls, 12 sxs gel, 110 sxs 60/40 poz, 4% gel.

Plugging Proposal Received by District #2 Office  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 Day: 6 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT A 35 sk plug of cement was pushed to 1411. The 4 1/2" was  
shot off and recovered. The top was squeeze plugged by pumping 200# of  
hulls, 12 sxs of gel and 110 sxs of 60/40 poz 4% gel through the 8 5/8"  
surface casing.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 18 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied #2499 MX 500 SI 200  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 8-21-87  
INV. NO. 17908

Signed [Signature]  
(TECHNICIAN)