

9-14

RECEIVED
KANSAS CORPORATION COMMISSION 2-

OCT 01 1993

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-095-21,650-0000
C SW SE, SECTION 21 TOWNSHIP 27 RANGE 10W

OPERATOR LICENSE # 30510 660 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR LARRY BAULDING
NAME & 416 EAST BLAINE
ADDRESS PRATT, KS 67124

LEASE NAME: MCNAMEE # 1-21
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4150' 134.87
PIPE: _____

SURFACE CASING: 8-5/8" @ 268'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: CHASE, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: DAVID
COMPANY NAME: KELSO CASING PULLING PHONE: _____

WERE: PBTD 4107' - 4-1/2" @ 4145' - PERFS 4006'-4020'
SAND BACK TO 3950' & 4 SX - RECOVER PIPE - 35 SX @
1450' - 35 SX @ 950' - CIRC CMT 320'

PLUGGING PROPOSAL RECEIVED BY: DISTRICT #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 12:30 DAY: 14 MONTH: 9 YEAR: 1993

ACTUAL PLUGGING REPORT:
PERFS COVERED W/SAND TO 3950' & CAPPED W/4 SX CMT -
4-1/2" CSG SHOT LOOSE @ 3217' & PULLED TO 1440' & 35 SX
CMT SPTD THRU CSG - 4-1/2" PULLED TO 940' & 35 SX CMT
SPOTTED THRU CSG - 4-1/2" CSG PULLED TO 320' & CMT CIRC
TO SURF - REMAINING CSG PULLED FROM WELLBORE & CMT
TOPPED OFF.

REMARKS: HOWCO 60/40 6% #509515

I DID OBSERVE THIS PLUGGING.

INVOICED


Steve Van Gieson (AGENT)

DATE 10-4-93

TRK. NO. 38840

9-14