

RECEIVED
KANSAS CORPORATION COMMISSION

2-100762

151
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

FEB 28 1992 2-12
2-28-92
CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-155-21,189-0000

100' E C E/2 NE, SECTION 36 TOWNSHIP 25 RANGE 10W

OPERATOR LICENSE # 9354

3860 FEET FROM S SECTION LINE

560 FEET FROM E SECTION LINE

OPERATOR Central Energy Corp.

NAME & Box 47590

ADDRESS Wichita, KS 67201-7590

LEASE NAME: Gordan #1

COUNTY: Reno

WELL TOTAL DEPTH: 3990'

PIPE:

SURFACE CASING: 8-5/8" @ 260'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A ☒ X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: White & Ellis Drilling, Inc.

ADDRESS: Eldorado, KS

LICENSE: 5420

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 12 MONTH: 2 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Judy

COMPANY NAME: White & Ellis Drilling, Inc.

PHONE: _____

WERE: 35 sx @ 1380' - 35 sx @ 900' - 35 sx @ 310' - 25 sx @ 60' - 10 sx RH

PLUGGING PROPOSAL RECEIVED BY: Don Thompson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (☒ X)

COMPLETED: HOUR: 9:25a DAY: 12 MONTH: 2 YEAR: 1992

ACTUAL PLUGGING REPORT:

Filled hole w/mud & pulled drl pipe to 1380' -
spotted 35 sx cmt - pulled pipe to 900' & spotted 35
sx cmt - pulled pipe to 310' & spotted 35 sx cmt -
pulled pipe to 60' & circ 25 sx cmt - put 10 sx cmt in
rat hole.

REMARKS: B.J. Titan #060400 60/40 2% gel

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 3-3-92

INV. NO. 34670

J. L. Sanders

(AGENT)

FORM CP-2/3
REV. 3/90