

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 207B
Wichita, Kansas 67202

API NUMBER: 15-155-21246-0000

C NW SW, SECTION 25 TOWNSHIP 25 RANGE 10W

OPERATOR LICENSE # 31160 1980 FEET FROM S SECTION LINE
OPERATOR Phillips Expl. Co. LC 4620 FEET FROM E SECTION LINE
NAME & 2338 Bromfield Circle
ADDRESS Wichita, KS 67226

LEASE NAME: Linder

COUNTY: RN

WELL TOTAL DEPTH: 4190'

PIPE: 5 1/2 @ 4047

SURFACE CASING: 8 5/8 @ 188

12/8

136.18

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: DS&W Well Servicing Inc.

ADDRESS: PO Box 231 LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 1030 DAY: 08 MONTH: 12 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM: Bryon

COMPANY NAME: DS&W Well Servicing PHONE: 316-587-3361

WERE: Sand to 3845 with 5 sx. 35 sx to 1400. 35 sx to 900. 300' to 0'

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)

COMPLETED: HOUR: 1230 DAY: 08 MONTH: 12 YEAR: 99

ACTUAL PLUGGING REPORT: Sanded bottom to 3845 with 5 sx of common. Shot 5 1/2" casing off at 1800'. Pulled to 1400'. Pumped 35 sx. Pulled to 900'. Pumped 35 sx. Pulled to 300'. Circulate cement to surface.

REMARKS: Allied #2700 60/40 4%

INVOICED

DATE 11/20/00

INV. NO. 061148

RECEIVED
KANSAS CORPORATION COMMISSION
1-18-00
JAN 18 2000
WICHITA, KS
CONSERVATION DIVISION

I DID NOT OBSERVE THIS PLUGGING.

Jack Luthi
PIRT NAME

FORM CP-2/3
REV. 3/90

(R)