

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

## WELL PLUGGING RECORD

Pratt County, Sec. 19 Twp. 27 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW NW

Lease Owner Clay Newell

Lease Name Justice Well No. 3

Office Address Stafford, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5/11/70 19

Plugging completed 5/14/70 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4366 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand from 4366' to 4300'. Run 5 sacks of cement from 4300' to 4270'.

Pumped 15 sacks of gel mud & 100 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn &amp; Smith Pipe Pulling Co.

Address Box 156 Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Stafford, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.


(Signature) Clay Newell

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of July, 1970

My commission expires 5-10-72

Glenn H. Chiles  
Notary Public.



# DRILLERS LOG

Justice B #3

Loc: NE SW NW  
Sec: 19-27-12W  
Pratt County, Kansas  
Operator: Cooperative Refinery Ass'n  
Contractor: Company Rig #5

Elevation: 1880 D.F.  
Casing: 10 3/4" O 435 w/300 Ex. Pos  
100 sax w/2 sax C C  
200 sax w/1 3/8" Flossal  
5 1/2" O 3499.79' w/150 sax.

Comm: 3-6-54 Comp: 3-27-54  
R T D 4356

From	To	Formation
0	10	Surface
10	125	Sand & Shale
125	400	Shale Red Bed & Shells
400	437	Red Bed
437	545	Red Bed Shale
545	1200	Shale Sand Shale
1200	1650	Shale Salt & Shells
1650	1990	Shale & Lime
1990	2080	Lime & Shells
2080	2220	Shale & Lime
2220	2405	Lime
2405	2960	Shale & Lime
2960	3025	Lime
3025	3415	Shale & Lime
3415	3435	Lime
3435	3785	Shale & Lime
3785	3820	Lime
3820	3905	Shale & Lime
3905	4200	Lime Shale & Chert
4200	4225	Lime Chert
4225	4250	Cherty Lime
4250	4275	Lime
4275	4328	Simpson Sand
4328	4366	Shale
	4366	R T D

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(STATE OF KANSAS )  
(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the  
Justice B #3 well, located NE SW NW of Section 19-27-12W, Pratt County, Kansas

Subscribed and sworn before me this 30 day of March 1954.

My commission expires: August 12, 1957