

STATE OF KANSAS
STATE CORPORATION COMMISSION
All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Pratt County, Sec. 19 Twp. 27 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Aylward Drilling Company
Lease Name Helmke "A" Well No. 2
Office Address 813 1st Nat'l Bank Bldg. - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 29 19 60
Application for plugging filed October 29 19 60
Application for plugging approved October 29 19 60
Plugging commenced October 29 19 60
Plugging completed October 29 19 60
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4371 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	282	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 240 ft.
Set plug at 240 ft. with hulls and 20 sacks
cement through drill pipe
Mud to 30 ft.
Set plug at 30 ft. with hulls and 10 sacks
cement through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

6-27-62 JUN 27 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 1st Nat'l Bank Bldg. - Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams
813 1st Nat'l Bank Bldg. - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1960

My commission expires December 11, 1961

Duane Jessup
DUANE JESSUP Notary Public.

HELMKE "A" NO. 2

Casing Record: 8 5/8" - 282'
 Company: Aylward Drilling Company
 Contractor: Aylward Drilling Company
 Location: SE SW SW 19-27-12W
 Pratt County
 Kansas
 Commenced: October 17, 1960
 Completed: October 29, 1960
 Elevation: 1889 DF - 1892 KB

	From	To	Remarks
Sand, some Clay	0	146	Set 8 5/8" surface pipe @ 282'
Red Bed	146	250	w/235 sacks cement
Shale & Red Bed	250	282	
Red Rock & Shale	282	430	Geological Tops:
Red Bed, Shale & Shells	430	1385	
Shale	1385	1727	Brown Lime 3740
Shale & Lime	1727	1800	Lansing 3760
Lime & Shale	1800	1870	B/Kansas City 4100
Lime	1870	2020	Marmaton 4116
Lime & Shale	2020	2205	Miss. 4198
Lime	2205	2590	Kinderhook 4228
Lime & Shale	2590	3050	Viola 4239
Shale, some Lime	3050	3140	Simpson 4309
Shale & Lime	3140	3290	Simpson Dolo. 4315
Lime & Shale	3290	3665	Simpson Sand 4339
Sand, Lime & Shale	3665	3800	
Lime	3800	4225	DST 3787-3810 Open 1 hr. Str. Bl.
Chert	4225	4240	Rec. 630' gas in pipe, 90' GCM,
Lime & Chert	4240	4310	240' HO&GCM, 120' OCWtryM, 60' SW
Sand & Shale	4310	4347	IBHP 1340#/20" - FBHP 1190#/30"
Lime	4347	4371 T.D.	FP 230# - 265#

DST 4305-27 Open 30" - Wk bl/21"
 Rec. 15' mud. IBHP 0#/20" -
 FBHP 0#/30". FP 0-0#

DST 4317-37 Open 30" - no blow
 Rec. 15' mud. IBHP 0#/20" -
 FBHP 0#/30". FP 0-0#

DST 4319-71 Open 30" - Wk Bl/21"
 Rec. 30' mud. IBHP 500#/20" -
 FBHP 0#/30". FP 0-0#.

RECEIVED
 STATE CORPORATION COMMISSION

JUN 27 1962

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Subscribed and sworn to before me this 2nd day of November, 1960

My commission expires December 11, 1961

Charles O. Williams

Duane Jessup
 DUANE JESSUP