


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 19 Twp. 27 Rge. 12 (E) (W)
Location as "NE/CNW%SW%" or footage from lines NE NW SW
Lease Owner Arthur Finston & Co.
Lease Name HELMKE Well No. 2
Office Address Orpheum Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-20-54 19
Application for plugging filed 11-18-57 19
Application for plugging approved 19
Plugging commenced 11-23-57 3 - 19
Plugging completed 11-25-57 19
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 9-7-57 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Irives
Producing formation Simpson Sand Depth to top _____ Bottom _____ Total Depth of Well 4385 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	350'	8-5/8"	350'	None
				5 1/2"	4380'	3657'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/crushed rock to 4225', dumped 5 sax cement @ 4225' w/dump bailer. Top of cement, 4195'. Pumped in 25 sacks Cel-Mud & 100 sacks cement through 8-5/8" surface casing by Globe Cementing Co. to plug well.

1-28-58
JAN 28 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Earl Miller
Address Great Bend, Kansas License # 12

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. H. Peachee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Peachee W. H. Peachee
Orpheum Building Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 58

My commission expires 7/28/58
Raymond J. Linner Notary Public.

PLUGGING
FILE SEC. 19 T. 27 R. 12 W.
BOOK PAGE 61 LINE 35

W E L L L O G

OPERATOR:	OIL PROPERTY MANAGEMENT 603 ORPHEUM BUILDING WICHITA, KANSAS	FARM NAME:	#2 HELMKE
CONTRACTOR:	SCHAFFER DRILLING Co. PRATT, KANSAS	LOCATION:	NE NW SW SEC. 19-27S-12W PRATT Co., KANSAS
CASING:	8-5/8" AT 350' 5-1/2" @ 4380'	COMMENCED:	6-24-54
R.T.D.	4385'	COMPLETED:	7-20-54
		PRODUCTION:	OIL-- SIMPSON
		ELEVATION:	1873 KB

FORMATION RECORD

DEPTHS SHOWN INDICATE BOTTOM OF FORMATIONS ENCOUNTERED.

CELLAR	8'	LIME	4080'
SOIL AND CLAY	35'	SHALE	4090'
SAND	70'	LIME	4110'
SHALE	350'	LIMEY SHALE	4112'
SHALE AND SHELLS	1700'	LIME	4140'
LIME	1800'	SHALE & LIMEY SH.	4185'
SHALE & SANDY SHALE	2200'	CHERTY LIME	4220'
LIME AND SHALE	2900'	SHALE	4222'
LIME	3000'	CHERTY LIME	4270'
SAND AND SHALY SD.	3200'	SANDY SHALE	4282'
LIME	3240'	SAND	4300'
LIME	3400'	SHALE	4302'
SHALE AND SANDY SH.	3460'	SAND	4310'
SHALE	3540'	SHALEY SAND	4312'
SAND & SANDY SHALE	3640'	SAND	4343'
SANDY SHALE	3710'	SANDY SHALE	4349'
LIME	3830'	SAND	4354'
SHALE	3840'	SANDY SHALE	4385'
LIME	4050'		

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1957
CONFIDENTIAL DIVISION
WICHITA, KANSAS

CERTIFICATION

STATE OF OKLAHOMA)
) SS:
COUNTY OF TULSA)

PLUGGING
FILE SEC. 19. T. 27. R. 12W
BOOK PAGE 61 LINE 35

I, ARTHUR FINSTON, UPON OATH STATE THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG OF THE OIL PROPERTY MANAGEMENT #2 HELMKE.

Arthur Finston
ARTHUR FINSTON

SUBSCRIBED AND SWORN TO BEFORE ME THIS 2nd DAY OF Dec., 1957.

MY COMMISSION EXPIRES May 25, 1961

Jenna Duncan
NOTARY PUBLIC

REC'D DEC 1 1957

MILLER CASING PULLING COMPANY

POST OFFICE BOX 711

TELEPHONE GLadstone 3-3762

GREAT BEND, KANSAS

Plugging Record For Oil Property Management Inc., Helmke Farm, Well #2:

Plugged back w/crushed rock to 4225', dumped 5
sax cement @ 4225' w/dump bailer. Top of ce-
ment, 4195'. Pumped in 25 sax Gel-Mud & 100
sax cement through 8 5/8 surface casing by
Globe Cementing Co. to plgg well.

Completion Date: 11-25-57

State Plugger: Merle Rives
Pratt Kansas.

Our KansasState Well Plugging License #12

PLUGGING			
FILE	SEC	19 T. 27 R. 20	
BOOK	PAGE	61	LINE 35

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1957
CONSERVATION DIVISION
Wichita, Kansas