


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

15-151-10252-0001  
Form CP-4

NORTH



Locate well correctly on above  
Section Plat

Pratt County, Sec. 19 Twp. 27 Rge. 12 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner Clay Newell  
Lease Name Seidel Well No. 3  
Office Address Stafford, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 4/17/70 19\_\_\_\_  
Plugging completed 4/23/70 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Beberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4355 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PULLED OUT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Sand from 4355' to 4300'. Run 5 sacks of cement from 4300' to 4270'  
Pumped 15 sacks of gel mud & 100 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address Box 156 Ellinwood, Ks. 67526

STATE OF Kansas COUNTY OF Stafford, ss.  
Clay Newell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clay Newell  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 8th day of May, 1970  
Lawrence H. Chiles  
My commission expires 5-10-72



BEARDMORE DRILLING COMPANY  
#3 SEIDEL  
NW SE NW Section 19-27S-12W  
Pratt County, Kansas

Operator Beardmore Drilling Company  
Date Drilling Commenced: 1-28-54  
Date Drilling Completed: 2-15-54

Casing Record:

8-5/8" set at 347' with 225 sacks cement on 1-28-54.  
5-1/2" set at 4355' with 173 sacks cement on 2-15-54.

Elevations:

1876 KB

<u>FORMATIONS</u>	<u>DEPTH</u>
Sand, Shale and Shells	150
Shale and Shells	347
Red Bed	670
Anhydrite	685
Red Bed	1050
Shale and Shells	1810
Lime	1925
Shale and Lime	2350
Shale and Shells	2470
Shale	2800
Shale and Shells	2895
Shale and Lime	3295
Shale and Shells	3395
Shale and Lime	3530
Lime	3595
Shale and Lime	3636
Lime	3922
Dense Lime	3965
Lime	4070
Lime and Shale	4130
Lime	4165
Lime and Chert	4236
Chert, Shale and Lime	4275
Sand	4395
Sand and Shale	4355
Total Depth	4355

TOPS

Kansas City	3718
Mississippi	4166
Kinderhook	4185
Viola	4218
Simpson Sand	4292

STATE OF KANSAS )

COUNTY OF SEDGWICK )

ss:

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

BEARDMORE DRILLING COMPANY

By W. B. Beardmore

Subscribed and sworn to before me this 31st day of July, 1959.

My commission expires: April 9, 1960.

Barbara Springsteen  
Barbara Springsteen - Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
APR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas