

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202.

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-22,049-0000

LEASE NAME Caspari

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

330' Ft. from S Section Line

2137' Ft. from E Section Line

SEC. 19 TWP. 27 RGE. 12 or (W)

COUNTY Pratt

LEASE OPERATOR Honey Oil Co., Inc.

ADDRESS 401 East Douglas - Suite 505 Wichita, KS 67202

PHONE# (316) 265-7300 OPERATORS LICENSE NO. 30080

Date Well Completed 5-20-91

Character of Well D&A

Plugging Commenced 5-20-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-20-91

The plugging proposal was approved on 5-17-91 (date)

by Richard Lacey (KCC District Agent's Name).

to be filed

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @ 660' w/75 sacks cement thru drill pipe

Next Plug: @ 280' w/75 " " " " " " 15 sacks in Rat Hole

Top Plug: @ 40' w/15 " " " " " " fill up water well w/cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Honey Oil Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(Employee of Operator) or ~~Owner~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530


SUBSCRIBED AND SWORN TO before me this 24<sup>th</sup> day of May, 19 91

Paula Ann Laudick  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

MAY 28 1991

CONSERVATION DIVISION  
Wichita, Kansas MY Commission Expires:



Form CP-4  
Revised 05-88

DRILLER'S WELL LOG

DATE COMMENCED: May 14, 1991  
DATE COMPLETED: May 20, 1991

Honey Oil Co., Inc.  
**CASPARI #1**  
Approx. C E/2 SW SW SE  
Sec. 19, T27s, R12W  
Pratt County, Ks.

0 - 130' Surface Soil, Clay, Sand  
130 - 643' Red Bed  
643 - 661' Anhydrite  
661 - 1765' Red Bed & Shale  
1765 - 3550' Shale & Lime  
3550 - 3555' Shale  
3555 - 3580' Lime & Shale  
3580 - 3729' Shale  
3729 - 3749' Lime & Shale  
3729 - 4089' Lime  
4089 - 4203' Shale & Lime  
4203 - 4324' Chert & Lime  
4324 - 4360' Shale  
4360' RTD

ELEVATION: 1862' K.B.

Surface Pipe: Set used  
10-3/4", 33# pipe @250'  
w/175 sacks 60/40 pozmix  
2% gel 3% cc.


**A F F I D A V I T**

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 24<sup>th</sup> day of May 1991.



*Paula Ann Laudick*  
Notary Public

RECEIVED  
STATE COOPERATION COMMISSION

MAY 28 1991

CONSERVATION DIVISION  
Wichita, Kansas