


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County, Sec. 21 Twp. 27S Rge. 18W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NW NW

Lease Owner Dunne-Gardner Petroleum, Inc.  
Lease Name Burkhardt Well No. 1  
Office Address Suite 250, 200 West Douglas, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry hole



Locate well correctly on above  
Section Plat

Date Well completed January 28 1978  
Application for plugging filed January 28 1978  
Application for plugging approved January 28 1978  
Plugging commenced January 28 1978  
Plugging completed January 28 1978  
Reason for abandonment of well or producing formation  
Dry hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 4915  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	415'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Mud to 410', 35 sacks cement  
Mud to 40', plug, 1/4 sack hulls, 12 sacks cement  
3 sacks cement in rat hole

FEB 16 1978  
2-16-78

CONSERVATION DIV.  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Don Gardner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

*Don Gardner*  
Suite 250, 200 West Douglas, Wichita, KS  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 1978

*Kathleen L. Aurburn*  
Notary Public.

My commission expires January 4, 1981

DRILLERS LOG

#1 Burkhardt  
C NW NW Section 21-27S-18W  
Kiowa County, Kansas

OPERATOR: DUNNE-GARDNER PETROLEUM, INC.  
Suite 250, 200 West Doulgas  
Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.  
Suite 250, 200 West Douglas  
Wichita, Kansas 67202

COMMENCED: January 18, 1978

COMPLETED: January 28, 1978

CASING RECORD: 8-5/8" @ 415' w/375 sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	100	Sand and shale
100	210	Red bed
210	415	Blue shale
415	1000	Shale and red bed
1000	1150	Shale and shells
1150	1178	Red bed shale
1178	1205	Anhydrite
1205	4225	Lime and shale
4225	4350	Lime
4350	4470	Lime and shale
4470	4915	Lime
4915		Rotary total depth

RECEIVED  
STATE CORPORATION COMMISSION

FEB 16 1978

STATE CORPORATION COMMISSION  
Wichita, Kansas


STATE OF KANSAS )  
                          ) ss  
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

  
Don Gardner

Subscribed and sworn to before me this 7th day of February, 1978.

My appointment expires:  
January 4, 1981

  
Kathleen L. Durbin  
Notary Public