


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 20 Twp. 27S Rge. 17WE/4W
Location as "NE/CNW1/4SW1/4" or footage from lines _____

C-NE NE SW
Lease Owner Kansas Ka-Tex Joint Venture
Lease Name Taylor Well No. 2
Office Address Mr. T. Blount, P.O. Box 48, Fellsburg, KS
Character of Well (Completed as Oil, Gas or Dry Hole) KS
Dry Hole 67048
Date Well completed June 16, 1979
Application for plugging filed Verbal Application 1979
Application for plugging approved Verbal Approval 1979
Plugging commenced June 16, 1979
Plugging completed June 16, 1979
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5,075'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED			8-5/8"	401'	None
	STATE CORPORATION COMMISSION					
		JUN 26 1979	6-26-79			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 5,075 ft. (rotary total depth) to 390 ft. Set plug at 390 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 390 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.


Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Notary Public of owner)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1979

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Kansas Ka-Tex Joint Venture

SEC. 20 T. 27S R. 17W

FARM Taylor

NO. 2

LOC. C-NE NE SW

COUNTY Kiowa

ROTARY TOTAL DEPTH 5,075'

COMM. June 5, 1979

COMP. June 16, 1979

CONTRACTOR H-30, Inc. (Rig #5)

ISSUED June 25, 1979

CASING

10 3/4"

8 5/8" Set at 401' cemented w/350 sxs cement

5 1/2"

4 1/2"

ELEVATION 2,154' O.L.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	418'
Shale	605'
Shale and Lime	1,435'
Red Bed and Shale	1,751'
Shale and Lime	2,449'
Lime and Shale	2,690'
Shale	2,911'
Shale and Lime	3,163'
Lime and Shale	3,685'
Shale and Lime	3,950'
Lime and Shale	4,267'
Shale and Lime	4,407'
Lime and Shale	4,510'
Lime	4,655'
Lime and Shale	4,885'
Lime	5,075'
Rotary Total Depth	5,075'

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1979

CONSERVATION DIVISION,
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 25th day of June, 1979.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982