

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KIOWA County, Sec. 20 Twp. 27 Rge. 17 (SE/ W NW)

Location as "NE/CNW/SW" or footage from lines SW NE NW

Lease Owner Wichita Iron & Metals Corp.

Lease Name RICH Well No. 1

Office Address Box 2421, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed August 19, 19 57

Application for plugging filed August 7, 19 61

Application for plugging approved August 8, 19 61


Plugging commenced August 17, 19 61

Plugging completed: August 21, 19 61

Reason for abandonment of well or producing formation depleted - non-producting

If a producing well is abandoned, date of last production: unknown 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Mississippi Depth to top 4680 Bottom 4751 Total Depth of Well 4751 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	409'	None
				5-1/2	4748	3195'
Log Attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 4751' to 4660', ran 5 sacks of cement from 4660' to 4625'. Mudded from 4625' to 300', rock bridge 300' to 290'. Ran 20 sacks of cement from 290' to 230'. Mudded from 230' to 35' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

10-30-62 OCT 30 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co., Ellinwood, Kansas
Address _____

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ray Stekoll, d/b/a Wichita Iron & Metals Corp. (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Wichita Iron & Metals Corp.

(Signature) By: Ray Stekoll
Ray Stekoll
Box 2421, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 62

Evelyn V. North
Evelyn V. North Notary Public.

My commission expires Dec. 22, 1962



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- AMERADA PETROLEUM CO.
Farm- Eunice Rich No. 1

SEC. 20 T. 27 R. 17W
SW NE NW

Total Depth. 4751'
Comm. 8-1-57 Comp. 8-19-57
Shot or Treated.
Contractor. D & M Drig.
Issued. 12-7-57

County Kiowa
KANSAS



Elevation. 2158'

Production. 500,000 CFG

CASING:

8 5/8" 409' cem w/300 sx.
5 1/2" 4748' cem w/150 sx.

Figures indicate Bottom of Formations.

sand	165
sand, stone & shale	413
red bed	465
shale, red bed & shells	1080
Anhydrite	1115
shale & shells	1525
shale, shells & salt	1750
shale & lime	1840
lime & shale	2090
lime	2485
lime & shale	3790
lime	3840
lime & shale	3965
chalky lime, lime & sand	4007
lime & sand	4075
lime & shale	4170
lime	4455
lime & shale	4487
lime	4560
lime & shale	4597
lime	4625
lime & chert	4735
sand & chert	4751
Total Depth	

TOPS:

Heebner	3974
Toronto	3991
Douglas	4002
Brown Lime	4122
Lansing	4140
Base Kansas City	4459
Marmaton	4468
Mississippi	4680
Kinderhook Shale	4721
Kinderhook Sand	4728