

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP 1

Take All Information Completely
Make Required Entries in
Mailing Labels Report to
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217

Kiowa County, Sec. 20 Twp. 27 Rge. 17W (X) X (W)

Location at "NE/CNW/SE/SW" of footage from lines NW NW NW
T. T. & A. Drilling
Lease Owner: T. T. & A. Drilling
Lease Name: TAYLOR Well No. 1
Office Address: Route # 2, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 14 1975
Application for plugging filed February 13 1975
Application for plugging approved February 13 1975
Plugging commenced February 14 1975
Plugging completed February 14 1975
Reason for abandonment of well or producing formation Dry Hole

Section Plat grid for locating the well.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Bieberstien
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4765 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 250' w/ 35 sacks cement thru drill pipe.
Top plug @ 40' w/ 1/2 sack hulls and 10 sacks cement. 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1975
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Duke Drilling Company (If additional description is necessary, use BACK of this sheet)
Address P. O. Box 823, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON ss.
Leonard Williamson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn in oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
P. O. Box 823, Great Bend, Kansas (Address)

Subscribed and sworn to before me this 14th day of February 1975

My commission expires April 11, 1978
Dorothy M. Hague Notary Public.

DRILLERS' WELL LOG

DATE COMPLETED: February 3, 1975
 DATE COMPLETED: February 14, 1975

T. T. & A. Drilling
 TAYLOR # 1
 NW NW NW Sec. 20-127-117N
 Kiowa County, Kansas

ELEVATION: 2166 E.S.

0 - 185' Sand, Surface Clay
 185 - 370' Clay, Sand Streaks
 370 - 468' Red Bed
 468 - 488' Anhydrite
 488 - 1085' Red Bed
 1085 - 1105' Anhydrite
 1105 - 1670' Red Bed, Shale
 1670 - 2140' Shale, Shells
 2140 - 3978' Lino, Shale
 3978 - 3993' Shale
 3993 - 3993' Lino, Shale
 3993 - 4015' Lino
 4015 - 4123' Shale
 4123 - 4138' Lino and Shale
 4138 - 4462' Lino
 4462 - 4688' Lino, Shale, Chert
 4688 - 4718' Chert
 4718 - 4765' Shale and Sand
 4765' RTD

FORMATION TOPS

Anhydrite	1085
Heebner	3978
Toronto	3993
Douglas	4015
Brown Lino	4123
L. Kansas City	4138
Base K.C.	4462
Maraton	4478
Miss	4688
Kinderhook	4718
RTD	4765

SURFACE PIPE: Set 402' of
 8 5/8", 26# pipe w/350 sacks
 60/40 pozmix, 2# Gel, 3# cc.

A F F I D A V I T

STATE OF KANSAS }
 COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 14th day of February, 1975.

Deputy M. Hogue
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 18 1975
 CONSERVATION DIVISION
 (Wichita, Kansas)