

STATE OF KANSAS
COMMISSION
S. Market, Room 2078
Wichita, KS 67202
STATE CORPORATION COMMISSION

WELL PLUGGING RETURN
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME CUNNINGHAM "B" UNIT

WELL NUMBER 24

990 Ft. from N Section Line

330 Ft. from W Section Line

SEC. 25 TWP. 27 SRGE. 11 (S or W)

COUNTY PRAIRIE COUNTY

Date Well Completed _____

Plugging Commenced 9-23-99

Plugging Completed 9-23-99

NOV - 1 1999

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
Wichita, Kansas

OPERATOR K.C. RESOURCES INC

ADDRESS P.O. BOX 1118 CARDIFF, CA 92007

PHONE 760-753-3330 OPERATORS LICENSE NO. 3880

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 9-20-99 (date)

By STEVE DURRANT (DOOGEE) (KCC District Agent's Name).

ACC-1 filed? N/A If not, is well log attached? _____

Producing Formation K.C. LANSING Depth to Top 3424' Bottom 3461' T.D. 3461'

Describe in detail the depth and thickness of all water, oil and gas formations.

Oil, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>K.C. LANSING</u>	<u>GAS OIL, WATER</u>	<u>SURFACE</u>	<u>327'</u>	<u>13"</u>	<u>327'</u>	<u>NONE</u>
<u>3424-3461'</u>		<u>SURFACE</u>	<u>3414'</u>	<u>8 5/8"</u>	<u>3414'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from _____ feet to _____ feet each set.
RUN TUBING DOWN TO 2600', SPOT 50 SAC CEMENT PLUG WITH 100 LBS OF COTTON SEED HULLS, PULL TUBING TO 600' - SPOT 50 SAC PLUG, PULL TUBING TO 300' - SPOT 50 SAC PLUG, PULL TUBING TO 30' CIRCULATE TO SURFACE - CEMENT RIG UP ON ANNULUS (13"-8 5/8") - PUMP 100 SAC CEMENT - SHUT DOWN PRESS 100 PSI TOOPOD OF 8 5/8" WITH 24 SACS CEMENT.

Name of Plugging Contractor PRAIRIE WELL SERVICE/UNITED COMMUNITY License No. _____

Address PRAIRIE, KS, EL DORADO, KS.

Name of Party Responsible for Plugging Fees: K.C. RESOURCES INC.

Date of 10-15-99 County of San Diego, ss.


ROD HOWLAND / Reiner Klawiter (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed, that the same are true and correct, so help me God.

(Signature) Paul Smith

(Address) 224 Birmingham Dr. Ste 1-A-1 Cardiff, CA 92007

Sworn to before me this 21 day of October, 1999.

Bobbi Duley Notary Public



My Commission Expires: July 2, 2003