

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSIONJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOCT 14 1963  
10-14-63  
CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Aylward Drilling Co.Complete Address: 909 1st National Bank Bldg., Wichita, KansasLease Name Helmke "A" Well No. # 1Location SW SW SW Sec. 19 Twp. 27 Rge. 12 (E) (W) WCounty Pratt Total Depth 4327Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Kent Well Servicing Co.Address: Box 470, Eldorado, Kansas License No. 394Operation Completed: Hour 9:00AM Day 12th Month Oct. Year 1963

The Above well was plugged as follows:

282' of 8 5/8" surface pipe, cemented to top. 4310' of 5 1/2" long string,  
cemented with 175 sacks. Bottom of hole was sanded to 4300', cemented  
with 5 sacks. Fluid was up in hole. Plug was pushed to 265', bridged  
with 15' rock. 5 sacks of cement was mixed in barrel and put on plug  
through dump bailer, and let set over night. Next morning hole bailed down  
and 20 sacks was added to the plug. Hole was filled with mud to 40', 10'  
rock bridge, cemented with 10 sacks to base cellar.

3300' of 5 1/2" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED  
 DATE 10/14/63  
 INV. NO. 9889-14

Signed: Archie Elving  
 Well Plugging Supervisor