

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

P

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 151 - 20626 - 0000 (of this well)

Operator's Full Name Stelbar Oil Corp., Inc.

Complete Address 200 W. Douglas, Suite 950, Wichita, Ks. 67202

Lease Name Atchison Well No. 1

Location C NW NW Sec. 19 Twp. 27 S Rge. 12 (E) (W) X

County Pratt Total Depth 3242

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 10 Am. Day 13 Month 10 Year 1979

The above well was plugged as follows:

401' 8 5/8" casing w/300 sax cement. 4 1/2" casing set at 2890' w/80
sax cement. Plug back to 2815'-Pref., at 2790'-94. Sun mixed & pumped
35 sax common cement in 4 1/2" casing to 2350' (top of cement) Pull 2240'
4 1/2" casing-Sun mixed & pumped 8 sax hulls-25 sax gel-125 sax 50/50
posmix cement w/4% gel & 3% cc to top of casing. Shut in w/400#.

RECEIVED
STATE CORPORATION COMMISSION
10-23-79
OCT 23 1979

I hereby certify that the above well was plugged as herein stated.

Signed: *[Signature]*
Well Plugging Supervisor

INVOICED
DATE 10-24-79
INV. NO. 0757-W