

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Pratt

Location: SW SE NW Sec. 19 Twp. 27 Rge. 12 (E) (W) X

Name of Field: _____ Total Depth: 4341

I have this date completed supervision of plugging of:

Lease Name: Siedel Well No. 4

Operator's Full Name: Beardmore Drilling Co.

Complete Address: 827 Beacon Bldg., Wichita, Kans.

Plugging Contractor: West Supply Co.

Address: Chase, Kans. License No. _____

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 1PM Day 4 Month October Year 1958

The above well was plugged as follows:

346' of 8 5/8" surface casing circulated with cement. TopnPerf.4309'.
Hole was filled to 4300' with sand and 5 sack cement dumped with dump
bailer on top sand. pipe was pulled from 4301'. Hole was filled to
359' with heavy mud. Rock bridge set at 359'. 20 sack cement placed on
top bridge from 340'. Hole was filled to 40' with heavy mud. A rock bridge
set from 40' to 30' with 10 sack cement placed to base of cellar.

Signed: *[Signature]*
Conservation Division Agent

Reviewed: *[Signature]*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 19 T 27 R 12 W
BOOK PAGE 131 LINE 9

RECEIVED
STATE CORPORATION COMMISSION
10-22-58
OCT 22 1958
CONSERVATION DIVISION