

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20825-0000K

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Ka Tex Energy

Complete Address R#2 Box 41 Lewis Kansas

Lease Name Ashworth Well No. 1

Location C-SE-SE Sec. 20 Twp. 27S Rge. 17W (East) (West)

County Kiowa Total Depth 4861'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling Co. Rig 77

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour: 11:45AM Day: 14 Month November Year: 1981

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

There is 426' of 8 5/8" surface casing cement circulated with 375 sbs of cement. 1st plug at 950' with 60 sbs of cement. 2nd plug pushed rubber plug to 400' with 50 sbs of cement on top of it. 3rd plug at 40' to 0' with 10 sbs of cement. Then pumped 10 sbs cement in rat hole & 5 sbs in mouse hole. The cement used was common with 2% Jell & 3% CC. The plugging was accomplished by Dowell well out of Great Bend Kan.

RECEIVED

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

DATE 12-11-81  
INV. NO. 8689-W  
NOV 17 1981  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Paul Luther  
Conservation Division Agent