

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 13, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Cunningham "B" Unit Well No. # 19

Location NE SE NE NE NE SE Sec. 25 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 3459'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 11:00AM Day 1st Month May Year 1967

The Above well was plugged as follows:

330' of 12½" surface pipe, cemented with 300 sacks. 3418' of 7" long string,
cemented with 500 sacks. This is an open hole. Bottom of the hole was sanded
to 3370', and cemented with 20 sacks. 1610' of 7" long string was recovered
from the hole. Bridge plug was pushed in fluid to 260', bridge plug and rock
bridge from 260' to 250'. 10 sacks of cement was mixed in a barrel, and put
on plug at 250', through the dump bailer, and let set over week-end. Hole
was bailed dry, and 30 sacks of cement was added to the plug. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 20 sacks to
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aurlie Elving
Well Plugging Supervisor

DATE 5/2/67

INV. NO. 5153-W