

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 13, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska 69001

Lease Name Cunningham "B" Unit Well No. # 21

Location App. C NW Sec. 25 Twp. 27 Rge. 11 (E) (W)W

County Pratt Total Depth 4055'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 12:00PM Day 10th Month June Year 1967

The Above well was plugged as follows:

396' of 10 3/4" surface pipe, cemented with 200 sacks. 4055' of 5 1/2" long string,
cemented with 300 sacks. Plug back T.D. 3500'. Top perferation 3430'. Bottom of
the hole was sanded to 3400', and cemented with 20 sacks, through the dump bail-
er. 1634' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed
in fluid to 300', bridge plug and rock bridge from 300' to 290'. 20 sacks of cem
ent was mixed in a barrel, and put on plug at 290', through the dump bailer, and
let set over-night, swagged in under water pressure. Next day hole was bailed
dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to
40', rock bridge from 40' to 30', and cemented with 15 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/14/67
INV. NO. 5392-W