

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

SEP 30 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Messman-Rinehart Oil Co.

Complete Address: 1432 Wichita Plaza, Wichita, Kansas

Lease Name Lion Fee "A" Well No. # 1

Location SE SE NW Sec. 21 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 4450

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:00 PM Day 26th Month Sept. Year 1963

The Above well was plugged as follows:

180' of 13 3.8" surface pipe, cemented to top. 4450' of 5½" long string,
cemented with 150 sacks. Plugged back to 3975'. Top perferation 3796',
Bottom of hole was sanded to 3780', cemented with 5 sacks. Fluid level
was up in hole. 25 sacks of Gel Mud and 20 sacks cement was pumped in
5½" pipe, through swage, at 324', 5½" pipe was pulled up to 212', and
cemented again with 25 sacks, through swage. Hole was bailed down to
30', bridge set at 30', 10' rock bridge, cemented with 20 sacks to base
cellar. 2908' of 5½" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

9/30/63

INV. NO.

9806-W

Signed:

Audie Elving
Well Plugging Supervisor