



Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name James A. Hershberger

Complete Address: 1039 1st National Bank Bldg., Wichita, Kansas

Lease Name Fairchild Well No. # 1

Location NE NE SW Sec. 21 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 4335

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 5:00PM Day 13th Month July Year 1963

The Above well was plugged as follows:

681' of 8 5/8" surface pipe, cement circulated. 3990' of 4 1/2" long string,
cemented with 125 sacks. Plugged back to 3820'. Top perferation 3786'.
~~Sandstone~~ Plug pushed to 3750', 10' rock bridge, cemented with 3 sacks.
Hole was filled to 250' with mud, 10' rock bridge, cemented with 20 sacks.
Hole filled with mud to 40', 10' rock bridge, cemented with 10 sacks to
base cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-17-63

INV. NO. 7425-w

Signed: Archie Elving
Well Plugging Supervisor