

Form CP-3
Rev. 6-26-62

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Gordan Morian, c/o Acid Engineers

Complete Address: 630 United Founders Tower, Oklahoma City, Oklahoma

Lease Name Crick Well No. # 1

Location C W/2 NE SE Sec. 14 Twp. 27 Rge. 11 (E) (W)

County Pratt Total Depth 3860'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:15 PM Day 3rd Month Sept. Year 1966

The Above well was plugged as follows:

307' of 8 5/8" surface pipe, cemented with 200 sacks. 3858' of 5 1/2" long
string, cemented with 75 sacks. Plug back T.D. 3835'. Top perferation 3810'.
Bottom of the hole was sanded to 3800', and cemented with 5 sacks, through
the dump bailer. 3155' of 5 1/2" long string was recovered from the hole. Bridge
plug was pushed in fluid to 300', rock bridge from 300' to 260'. 6 sacks of
cement was mixed in a barrel, and put on plug at 260', through the dump bail-
er, and let set over-night. Next day hole was bailed dry, and 24 sacks of
cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 9/6/66

INV. NO. 3865-4